


**DESHBANDHU COLLEGE
KALKAJI, NEW DELHI-110019**

Date: 18.11.2021

QUOTATIONS FOR INSTALLATION OF FLOOD LIGHTS IN VOLLEY BALL COURT


Sealed Quotations are invited for installation of Flood lights in Volleyball Court at Deshbandhu College with following specification. The Quotation must be addressed to "The Principal, Deshbandhu College, University of Delhi, Kalkaji, New Delhi – 110019 and reach by **29.11.2021**:

S. No.	Description of Work	Qty.	Unit	Rate	Amount
1	Excavation Work manually / by mechanically means including stacking and disposal of unserviceable material with in 50 Meters lead as per direction of Engineer in charge/ Committee	5	Cub. Mtr.		
2	Providing and fixing Of LED flood Light 100 watt (Jeta Iris) Make (in consultation with college committee)	6	No.		
3	Supply and laying with digging the ground upto .5 mtr depth and fixing accessory (as required) and re-fixing protection of underground cable as required, PVC Insulated aluminum armored cable of the size 2x25 mm	90	Mtr.		
4	Supplying and fixing of street MS tubular light pole of 6 mtr long 75 mm dia, 3 mm thick fixing in ground depth of 1 mtr. Excavation and re-fitting protection of ground as required . with 2.5 mm copper wiring.	6	No.		
5	Control Panel for controlling the electricity supply of poll With single bus bar and 63 amp MCB (6 No), 63 Amp DP 1 (N0.)With double door covering Mattel box with powder coated paint, floor mounted complete in all respect.	1	No.		
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (1 cement: 2 coarse sand (zone-III): 4 graded stone aggregate 20 mm nominal size).	5	Cub. Mtr.		
7	Providing and fixing 18 mm thick gang saw cut, mirror polished, pre molded and pre polished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, color and texture laid over 12 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. (Rosy Pink/Cheema Pink/ Udaipur green marble/ P White/ Tan Brown / Apple Green)	7	Sqr. Mtr.		
Total Amount (Inclusive of all taxes)					


Page 1 of 2

Terms & Conditions:

1. The quotations should contain the complete technical specifications.
2. The quotations should be valid for 120 days from the date of submission.
3. All prices quoted must be inclusive of GST and all taxes.
4. The College reserves the right to accept or reject or cancel any tender or modify or relax any part of the tender offer, without assigning any reason thereof.
5. The College reserves the right to award the work to the First Lowest Bidder (Successful Bidder) for the scope of the entire tender or an item wise basis.
6. The college has the right to cancel the tender at any point of time. Also competent authority can increase or decrease the quantity/items or work need to be done. The Competent authority can also select L1 items wise (whichever is lower) in comparative chart. The tender work executed by the selected bidder should be under minimum five-year warranty.
7. The college authorities can remove any items as well at any stage of the work.
8. The Rate contract shall remain valid for 12 months from the date of signing of contract. However, this may be extended further for the period approved by the college.
9. The Contractor should see the existing site and apprise themselves of all site conditions and complete scope of work.
10. If the successful bidder after receiving work order wants to extend any part of the work, it will have to take permission from the competent authority and the work will not exceed more than 10% of the above mentioned work.
11. Payment will be made only after the successful completion of the work as certified by the competent authority.


PRINCIPAL